

# **DeLuz Pipeline Replacement Job 3065**

## **ADDENDUM A**

*January 31, 2019*

Attention All Bidders:

The following clarifications, changes, and/or deletions to the Contract Documents are hereby made as part of the Contract Documents for the above referenced project as fully and as completely as though the same was included therein. This addendum shall be acknowledged on the face of the envelope submitted with the Bid Proposal.

This Addendum "A" includes clarifications and/or changes to the Contract Documents for the Fallbrook Public Utility District, **Job 3065, DeLuz Pipeline Replacement**

1. Per Specification Section 15076, CML&C Steel Pipe shall be fully engineered with shop drawings submitted and approved prior to manufacture of pipe. The layout schedule shall indicate the order of installation, the length and location (station and elevation) of each pipe section and special, the station and elevation of the pipe invert at all changes in grade, and all data on curves and bends for both horizontal and vertical alignment.
2. Per Drawing No. G-2, Water Notes #4, and Construction Note #5, Contractor shall pothole to verify the pipeline size, location, and depth at each tie-in location and utility crossing prior to submittal of shop drawings.